


Notes:

1. To enable Neutral / Earth Bond for Inverter output, link terminals GP1 and GP2.
2. Combi internal ground relay disconnects earth link when unit is connected to AC input source (shoreline).
3. Unit must be installed in accordance with BS7671 IET Wiring Regulations.
4. Initial Inspection and Testing:

The installing contractor must carry out complete inspection, testing and certification of the installation when complete and before being put into service. All testing shall be carried out and be in accordance with BS7671.

TITLE Kisae Inverter / Charger Connections	NOTES	ISSUE A	DATE 05/08/20	AUTH MH	MODIFICATION DESCRIPTION Initial Release		Merlin Equipment Limited, Clyst Court, Hill Barton Industrial Estate, Exeter, Devon, EX5 1 SA Tel: 01202 – 697979 www.merlinequipment.com	DRAWN MH	CHECKED
CLIENT Merlin Equipment	USED ON ASSY 1000 & 2000W	© 2019 Merlin Equipment Limited. This drawing remains the sole right and property of Merlin Equipment Limited. You may not make unauthorised copies or pass this information to third parties without the express written permission of Merlin Equipment Limited.				UNCLASSIFIED PROPRIETARY COMPANY CONFIDENTIAL	DATE 05/08/2020	DRAWING No. 1415	